

**VIJAYANAGARA SRI KRISHNADEVARAYA UNIVERSITY, BELLARY.**  
[ENGINEERING DEPARTMENT]



NO. VSKUB/ENGG/ Quo/Elect./2023-24/197

Date:20 -06-2024

**QUOTATION**

Sealed quotations subscribing the name of the Arranging L.T. Line Power Connections to Newly Constructed General Boys Hostel Building (GF, FF & SF) in the premises of Vijayanagara SriKrishnadevaraya University, Janansagara Campus, Ballari. So as to reach this office on or before 27-06-2024. and quotation should be addressed to Registrar, V.S.K. University, Vinayaknagar, Cantonment, Ballari.

**NAME OF WORK:-** ARRANGING L.T. LINE POWER CONNECTIONS TO NEWLY CONSTRUCTED GENERAL BOYS HOSTEL BUILDING (GF, FF & SF) IN THE PREMISES OF VIJAYANAGARA SRIKRISHNADEVARAYA UNIVERSITY, JANANSAGARA CAMPUS, BALLARI.

Sl. No	Particulars	Unit	Quantity	Rate quoted per unit	
				In figures	In words
A	B	C	D	E	F
	<b>MATERIAL PART</b>				
1	PSCC Pole - 9 Mtr Long, 200 Kg WL (Dwg No. BESCOM/ GM/ QS&S/50 Dtd 24.11.2018) as per REC Standards (Material Code: 200006)	No.	25		
2	LT 4 Pin Cross Arm - GI (Material Code: 280014)	No.	27		
3	PSCC Pole (200 Kg WL) Clamp - GI (Material Code: 279510)	No.	25		
4	Rabbit ACSR Conductor (Material Code: 284108)	Km.	3.60		
5	11 kV Ceramic Pin Insulator (Shell only) (Material Code: 283005)	No.	120		
6	11 kV GI Pin for 11 kV Ceramic Shell Insulator. (Material Code: 283055)	No.	120		
7	No. 08 Strain Insulator (Material Code: 283166)	No.	20		
8	Guy with Complete Set. (Material Code:2811101)	Set	6		
9	LT ST Support 50x6 mm Flat - GI (Material Code: 280091)	No	32		

A	B	C	D	E	F
	<b>LABOUR PART</b>				
1.a	Erection of RCC/PSCC Pole of 9 to 10 Mtr long in a pit of 1.8 Mtr depth.	No.	25		
1.b	Digging of Pit 1.8 Mtr depth for erection of 9 to 10 Mtr Long Steel/RCC/PSCC Poles. In Ordinary soil	No.	25		
1.c	Loading and unloading of Pole of 9 to 10 Mtr long	No.	25		
2	Fixing of 4 Pin cross arm with Insulator and Braces fixing.	No.	27		
3	Stringing of conductor Rabbit ACSR, binding of conductor on each insulator and dead ending on strain or disc/strain insulator by means of clamps.	Km	3.60		
4.a	Digging of Pit for GUY SET in Ordinary soil.	No.	6		
4.b	Fixing of GUY Set with break insulator making use of 7/3.15 mm (7/10 SWG) galvanised steel wire with turn buckle and anchoring arrangement as per approved drawing.	Set.	6		
5	Fixing of HT/LT Single Top Support	No	32		

I have read the terms and conditions for the above work and I shall abide by the same.

19/10/14  
REGISTRAR  
V.S.K.UNIVERSITY,  
BALLARI-583105.  
S. S. S.

**TERMS & CONDITIONS:**

1. The rates quoted should be excluding GST .
2. The right to reject the quotation is vested with University authorities.
3. The quoted rates should be valid at least for 03 months.
4. The GST should be paid separately.
5. The Contractor should have Class-III and above Electrical Licence from the competent authority.
6. The Successful Contractor should submit the EMD of Rs.11,125/- in the name of Finance Officer, VSK University, Ballari in the form of DD/Bankers Cheque payable at Ballari.
7. The Contractor Should have GST and PAN Certificates.

Copy:

- 1) The Director , ICT Department, VSK University, Ballari-583105 for necessary action to upload the quotation in university website for 07 days or up to last date.
- 2) Notice Board.