

VIJAYANAGARA SRI KRISHNADEVARAYA UNIVERSITY, BELLARY.
[ENGINEERING DEPARTMENT]



NO. VSKUB/ENGG/Quo/K S & B M/2026-27/ 314

Date : 6 -07-2026

QUOTATION

Sealed quotations subscribing the name FOR PROVIDING AND LAYING OF KERB STONES BESIDE PAVERS & CONSTRUCTION OF MASONRY DRAINS ALONG THE BHADRA BOYS HOSTEL & TUNGA GIRLS HOSTEL ROAD SIDE AT MAIN ROAD (HAGARI BOY'S HOSTEL) IN THE PREMISES VIJAYANAGARA SRI KRISHNADEVARAYA UNIVERSITY, JNANA SAGARA CAMPUS, BALLARI. So as to reach this office on or before 14.07.2026 and quotation should be addressed to Registrar, V.S.K. University, Vinayaknagar, Cantonment, Ballari.

NAME OF WORK:- FOR PROVIDING AND LAYING OF KERB STONES BESIDE PAVERS & CONSTRUCTION OF MASONRY DRAINS ALONG THE BHADRA BOYS HOSTEL & TUNGA GIRLS HOSTEL ROAD SIDE AT MAIN ROAD (HAGARI BOY'S HOSTEL) IN THE PREMISES VIJAYANAGARA SRI KRISHNADEVARAYA UNIVERSITY, JNANA SAGARA CAMPUS, BALLARI.

Sl No	Name of materials / Items or Work	Unit	Quantity	Rate quoted per unit	
				In figures	In words
1.	Earth work excavation for Foundation by mechanical means for all works & depth upto 3 m, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work In all kinds of soils Depth up to 3 m	m ³	94.50		
2.	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap / basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates	m ³	22.41		
3.	Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finished in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra) 600 x 300 x 150 mm size	m	270.00		
4.	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m ³ and minimum compressive strength of 4.00 N/mm ² conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. (The cost of PCC shall be paid extra)	m ²	48.00		
5.	Providing Water based glossy paint (Green certified product) to Kerb Stones as per IS 164:2015 technical specifications including cleaning & surface preparation.	m ²	81.00		

6.	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	m2	48.00		
	GST Extra				

I have read the terms and conditions for the above work and I shall abide by the same.

Rokun - b

REGISTRAR
V.S.K.UNIVERSITY,
BALLARI-583105.

K. D. K.

B. S. S.

TERMS & CONDITIONS:

1. The rates quoted should be excluding GST .
2. The right to reject the quotation is vested with University authorities.
3. The quoted rates should be valid at least for 03 months.
4. The rate quoted should be exclusive of GST , transportation, loading & unloading charges etc. complete.

Copy:

- 1) The Director , ICT Department, VSK University, Ballari-583105 for necessary action to upload the quotation in university website for 07 days or up to last date.
- 2) Notice Board.